

DRAFT 10-12-2017

CONSTRUCTION GUIDELINES FOR ONE NEW WATER-SUPPLY WELL

**MEINERS OAKS WATER DISTRICT
WELL No. 4 - Replacement
471-481 South Rice Road
Vicinity Ojai
Ventura County, California**

October 2017

Presented herein are the well drilling guidelines for one new water well to be drilled at the Meiners Oaks Water District (MOWD) property, Vicinity Ojai, Ventura County, California. The well site is within the area housing MOWD Well Nos. 4 and 7 between the Ventura River and Rice Road (Figures 1 and 2). This document is intended for bid solicitation only and is neither a direction to construct nor a final design document; field conditions will determine project build out and final costs based on line items presented in successful contractor's bid and the ultimate contract between MOWD and the selected contractor.

Replacement MOWD Well No. 4 (Figure 3) is to be drilled at an approximate elevation of 660 feet, with a latitude of 34.4464° N and a longitude of 119.2910° W. The well site is accessible via Rice Road and an unpaved private road beyond a locked gate to the MOWD facility. Anticipated design production rate in the new MOWD Well No. 4 is anticipated to be at least 1,000 gallons per minute (gpm).

The proposed 16-inch-diameter, stainless steel-cased well (Figure 4) is to be constructed in conformance with the guidelines outlined herein and in DWR Bulletin 74-90. The drilling contractor shall have a valid C-57 well driller's license and shall acquire or comply with all permits required from Ventura County and other agencies to drill the new well. The construction guidelines provided below apply to the new well, however, unit prices provided on the accompanying Bid Sheet shall be consistent for subsequent wells drilled on the property, if directed, or other wells on MOWD property or properties to which MOWD has access for well construction as part of this contract.

A copy of these guidelines and the Ventura County Well Permit shall be kept onsite at all times. A copy of the driller's report (DWR form 188) and four final copies of all geophysical logs shall be received by the geologist, Kear Groundwater (KG), within 21 days of well completion.

As presented in the transmitting electronic mail, a pre-bid meeting of **Wednesday December 33, 2033 at 10:00 AM** will allow prospective contractors to visit the planned well sites and present questions. Only addenda delivered to all prospective contractors in writing will be considered modifications to this set of bid guidelines.

**BIDS DUE BY 5:00 PM THURSDAY February 0, 2018 VIA E-MAIL to:
mike@meinersoakswater.com AND jordan@keargroundwater.com**





